

CONSTRUCTING S U M M I T THE EUROPE 2 0 2 1 OF TOMORROW




#WEMAKE2BUILD



Outline

1 Overview
2 Demos
3 "Bauen 4.0" solutions
4 Outlook











Project partners and organizational framework

Funding BMBF – Project Management Agency Karlsruhe – INKOWE program

Wacker Neuson

Group

- Duration July 2019 July 2022 extended to December 2022
- 22 industrial partners, 2 universities
- Accompanied by various associations
- Total costs 10 Mio. € / 5 Mio. € funding





























































Construction site challenges












The main topics




- Automation
- Assistance functions
- Remote control
- Environment recognition

connected mobile machines

Vertical Integration

- 5G machine and construction site connectivity
- Connectivity Solutions
- Cloud Technologies
- Reliable and secure data exchange



- Tracking & Tracing
- Simulation of construction processes
- BIM to BIMsite
- Driver guidance system 4.0

Integration of main topic solutions into a common construction demo scenario – end of project demonstration





2 Demos









SUMMIT 2021 BRUSSELS


Demos within the main topics

Automated digging

Automated tool change



Detection"as built" condition



> Environment recognition

Automated processes



Remote
Control

Townson

Mulit-Connectivity modul: WiFi, 5G, 4G, BLE...



Construction Site Networks: WiFi, 5G Campus






node 🚱

Tracking & Tracing of Material via LPWAN





Process optimization and progress prediction using simulation and machine data (e.g. with ISO 15143-3 data via OPC UA)



AR-based driver assistance: Visualization via HoloLens






via

Vertical Integration









3 "Bauen 4.0" solutions













OPC-UA based Bauen4.0 architecture

- OPC-UA data model and communication protocol
- Bauen 4.0 Specification for interoperable data model for construction equipment












Developed solutions in main topic 1










Developed solutions in main topic 2





Special 5G connectivity modul












Developed solutions in main topic 3



OPC UA data model for construction machines



All demonstrator machines are built up and the first automation functions have been tested










Developed solution: site information system

Mission data is submitted via OPC-UA interface

Topografic mission data in annotated LandXML in accordance with ISO 15143-4

- Automation specific annotations
 - geofences
 - trajectories
 - tracks
 - dump areas
 - target geometry





4 Outlook











Next Steps



Fabrikstraße 48, Dresden



- First 5G connectivity tests



Industrial area Zeißig, Hoyerswerda



- Test of excavator automation
- First tests with site information systems

- > Setup of 5G Campus Network
- Automation of machine interaction
- > Setup and test of the demo scenario



Industrial area Görlitz



Establishment of infrastructure and corporate organizational forms for use after the end of the project









SPONSORED BY THE



MANAGED BY



PTKA

Project Management Agency Karlsruhe

Karlsruhe Institute of Technology

-contact-

Prof. Dr.-Ing. Jürgen WeberChair of Fluid-Mechatronic Systems

: +49 351 – 463 33559



Imagefilm DE

Imagefilm_EN





Website



@bauen40





Thank you for your attention!

